



ELECTRICAL
MINING & INDUSTRIAL SUPPLIERS

EARTH LEAKAGE TEST KITS



PREWIRED – EARTH LEAKAGE TEST KITS

Retrofit kits for easy installation to existing load centres and Distribution boards

- IP66 Assembly c/w Kraus & Naimer Selector switch
- NHP 10kA circuit protection within pad lockable cover
- Flexicon PVC conduit fitted to bottom c/w glands
- 10A GPO with round pin earth
- Wire numbers and sleeves for easy identification
- Can be supplied with active only or active and neutral switching
- Wall mount brackets fitted for easy mounting
- Bezel labelling OFF,1,2,3,4,5,6 as standard
- Available in 6 or 11 way
- Prewired in 2.5mm tinned flexible cable
- RPEQ certified drawings can be provided at time of order

Assembled kit standard Part numbers

ACSELT06-1P-K&NB1612 – Off plus 6 way, Active only switching.

ACSELT11-1P-K&NB1612 – Off plus 11 way, Active only switching.

ACSELT06-2P-K&NB1612 – Off plus 6 way, A & N switching.

Optional

- Custom bezel numbering
- Custom wire numbering
- Optional cable exits, ie top, left or right
- Can be custom made with additional circuits if required

For Custom options please refer part number matrix below

CODE	CIRCUIT QTY	1P/2P SWITCH	SWITCH BRAND	ENTRY	CAM SWITCH BEZEL NUMBERING	FLEX CONDUIT LENGTH (mm)	CABLE LENGTH (mm)
ACSELT	06 = 6 WAY 11 = 11 WAY	1P = A 2P = A&N	K&N	T = TOP B = BOTTOM L = LEFT R = RIGHT	1 = OFF, 1,2 C = OFF, CB1, S = SPECIAL	2 = 200 6 = 600	12 = 1200 22 = 2200

EXAMPLE – **ACSELT06-1P-K&NT1212**

For further details please contact

Mark Jansz

Business Development Manager – Mining

Phone – 0438128583, Email – mark.jansz@mmem.com.au

53 – 55 Enterprise ST, Paget, Mackay QLD 4740. Phone: (07)49985100